



झिमरुक गाउँपालिका
JHIMRUK RURAL MUNICIPALITY



गाउँ कार्यपालिकाको कार्यालय
OFFICE OF THE RURAL MUNICIPAL EXECUTIVE

भ्यागुते, प्युठान
BHYAGUTE, PYUTHAN

लुम्बिनी प्रदेश, नेपाल
LUMBINI PROVINCE, NEPAL


प.सं २०८२/०८३

मिति - २०८३/०२/१९

विषय- बिषय- सिलबन्दी कोटेशन पेश सम्बन्धि सुचना ।

श्री सम्पूर्ण इच्छुक फर्म तथा सप्लायर्सहरु

प्रस्तुत विषयमा यस झिमरुक गाउँपालिका गाउँकार्यपालिका कार्यालय अन्तरगत निर्माण भएको सित भण्डारको सञ्चालनको तथा अपग्रेडिङ गर्नेकार्यको लागी BOQ तयार गरि यसै पत्र साथ सम्लग्न राखि पठाइएको छ तपाइको फर्मबाट के कतिदरमा उपलब्ध गराउन सकिन्छ उपलब्ध गराउने दरभाउ पत्र मितिले ७ (सात) दिन भित्र उपलब्ध गराइदिनुहुन अनुरोध छ।


२०८३/०२/१९
अमरराज सेजुवा
प्रमुख प्रशासकीय अधिकारी

“झिमरुक गाउँपालिकाको समृद्धिको आधार: व्यवसायिक कृषि, पर्यटन तथा वाणिज्य, सुरक्षित आवास र पूर्वाधार”

ईमेल : jhimrukmun@gmail.com , info@jhimrukmun.gov.np वेबसाइट: jhimrukmun.gov.np

झिमरुक गाउँपालिका

गाउँ कार्यपालिकाको कार्यालय

भ्यागुते, प्यूठान

लुम्बिनी प्रदेश, नेपाल

गाउँ कार्यपालिकाको कार्यालय

भ्यागुते,

BoQ

E/Y: 2082/083

S.N.	Item of Description	Units	Quantity	Rate (NRs)		Total Amount(NRs.)	Remark
				In Figure	In Word		
1.00	Supply and Installation Centrifugal Air Curtain High Speed 4 Feet, With Auto Cut Sensor Operation System While Door Opening	set	2.00				
2.00	Supply and Installation of PVC Curtain For Room 4 Feet 2 Mm Thickness, 12 Flap , Hin Metal	set	2.00				
3.00	Supply and Installation of Ultrasonic Humidifier System 7 Ltr/Hrs Mist Generator: Ultrasonic, Mist Partical: 0.05 Micron, Power Supply: 220-240V-50Hz, RH Level In Room: 90-95%, Water Supply: Fresh Water Supply below 100 TDS	set	2.00				
4.00	Supply and Installation of Co2 Damper Inline Fan System, 250 CFM, Manual Operation System, With In and Out System	set	2.00				
5.00	Supply and Fixing of 6 AMP 2 Pole MCB With Box all complete as per instruction of the site incharge .	set	4.00				
6.00	Supply and Fixing of 1 MM 3 Core Miltistand Wire with PVC lisy all complete as per instruction of the site incharge .	Mtr	80.00				
7.00	3*3 PVC Power Supply Box With 16 AMP Power Socket	set	1.00				
8.00	Supply and Installation of 25 Ltr Capacity Reverse Osmosis System for Water Supply on Humidification System with 3/4 Mm PVC Flexival Pipe and Necessary Connection On Machine	set	1.00				
9.00	Distribution Panel Board(Main 100A MCCB Control) With Bus Bar, Voltage Scanner and Display	set	1.00				
10.00	100 Amp Electrical Changeover, City and DG Line		1.00				

